# Proposal

**From:** Innovative Excavating, LTD
15 Conklin Drive
Stony Point, NY 10980
Contact: Jeffrey Conklin
Phone: 914-447-2987
Email: innovativeexcavatingltd@gmail.com

**To:** Ed Cook Contracting Inc.
9 Edward Street
Sparkill, NY 10976
Contact: Ed Cook
Phone: 845-359-4977
Fax: 845-359-2774

Project: SOUTH ORANGETOWN AMBULANCE - 251030
Description: South Orangetown Ambulance - Sitework
Bid Location: Independence Drive Blauvelt, NY
Bid Date: 10/30/2025
Revision Date:

| DESCRIPTION | BID QTY | U/M | | AMOUNT |
|---|---|---|---|---|
| **Site Preparation** | | | | |
| Mobilization * | 1.000 | ls | | |
| Erosion Control * | 1.000 | ls | | |
| Clear & Grub * | 1.000 | ls | | |
| Site Demolition & Disposal | 1.000 | ls | | |
| **Site Preparation** | | | **Section Total:** | **$30,500.00** |
| **House Demolition & Disposal** | | | | |
| Demolition - House | 1.000 | ls | | |
| Abandon Sewer & Water | 1.000 | ls | | |
| **House Demolition & Disposal** | | | **Section Total:** | **$19,600.00** |
| **Sitework** | | | | |
| Topsoil - Strip & Stockpile * | 1.000 | ls | | |
| Cut to Fill - | 1.000 | ls | | |
| Import & Place Structural Fill | 1.000 | ls | | |
| Site Grading | 1.000 | ls | | |
| Respread Topsoi | 1.000 | ls | | |
| **Sitework** | | | **Section Total:** | **$78,200.00** |
| **Site Concrete** | | | | |
| Curb - Belgium Block | 1.000 | ls | | |
| Sidewalk Concrete | 1.000 | ls | | |
| Retaining Wall | 1.000 | ls | | |
| **Site Concrete** | | | **Section Total:** | **$32,290.00** |
| **Trenching - Electric** | | | | |
| Electric Trench Pole to Panel | 1.000 | ls | | |
| Electric Trench Panel to Generator | 1.000 | ls | | |

# Proposal

| DESCRIPTION | BID QTY | U/M | | AMOUNT |
|---|---|---|---|---|
| Site Light Trenching | 1.000 | ls | | |
| **Trenching - Electric** | | | **Section Total:** | **$11,490.00** |
| **Foundation Excavation** | | | | |
| Foundation Excavate & Backfill | 1.000 | ls | | |
| Prep for SOG - 6" of 3/4 " Stone | 1.000 | ls | | |
| **Foundation Excavation** | | | **Section Total:** | **$22,000.00** |
| **Sewer Installation** | | | | |
| Pump Station - Environment 1 | 1.000 | ea | | |
| **Sewer Installation** | | | **Section Total:** | **$23,400.00** |
| **Drainage** | | | | |
| Roof Leader Drains - 6" | 1.000 | ls | | |
| Drainage - Crossing Independence Avenue | 1.000 | ls | | |
| Drainage - Onsite Pipe & Basins | 1.000 | ls | | |
| Drywell - Detention System | 1.000 | ea | | |
| **Drainage** | | | **Section Total:** | **$78,290.00** |
| **Paving Work** | | | | |
| Paving Access & Parking Areas | 1.000 | ls | | |
| Parking Lot Striping | 1.000 | ls | | |
| **Paving Work** | | | **Section Total:** | **$55,730.00** |
| | | | **TOTAL BID:** | **$351,500.00** |

# Project Comments

Notes:

Innovative will supply the necessary insurance.

Scope of work:

Site Preparation:

- mobilization
- site demolition and disposal. (asphalt, curb, sidewalk, drywell and fence)
- erosion control
- clearing and grubbing - (trees, stumps and brush)

# Proposal

House Demolition:
- removal and disposal of existing house. (as if no asbestos or other hazardous material exists)
- abandon sewer and water services.

Sitework:
- strip and stockpile topsoil
- cuts to fill
- import and place structural fill in all building and parking areas.
- site grading
- respread topsoil - existing topsoil will be respread only. Any processing, raking, etc by the landscape contractor)

Site Concrete
- concrete sidewalk
- belgium block curbing
- retaining wall between parking lot and drain collection area.

Electrical Trenching:
- primary from pole to panel.
- from panel to generator pad.
- site lighting including two pole bases

Building Excavation: (both buildings):
- footing excavation and backfill.
- 6" of stone for slab-on-grade

Sewer installation:
- "environment one" package station (top encased in a 48" diameter concrete manhole.
- 4" schedule 40 gravity piping
- 1 1/2" force main to manhole tie- in.
- 1" electrical conduit to 5' outside foundation.
- electrical hook-up by others.

(4" pipe and electrical conduit capped or tied into existing pipe - 5' outside foundation wall)
(existing block landscape wall to be removed and replaced by others to facilitate force main tie-in to existing manhole.
- blacktop trench restoration

Drainage includes:
- Independence Ave Crossing
  - sawcutting
  - traffic control
  - tie-in to existing drainage on south side of road.
  - concrete curb and sidewalk restoration.

- repave trench and crack seal cut lines.
- onsite drainage pipe and catch basins.
- drywell detention recharger system.

Access and Parking Lot Paving
- paving as per approved detail
- parking lot striping

Exclusions:

NYS Sales Tax - exempt certificate to be supplied by the Ambulance Corp.
Permits, if requested, will be supplied and billed at cost as additional.
SWPPP monitoring.
Temporary construction fencing.
Testing or inspection fees.
Asbestos survey and/or removal and disposal of any hazardous material.
Survey and/or stakeout.
Fencing
Trenching for under slab utilities.
Electrical hook-up of sewer pump station by others.
Footing drains (not shown).
Concrete garage entrance slab.
Foundation insulation or vapor barrier.
Winter protection.
Rock removal.

**Signature:** JEFFREY CONKLIN

**Jeffrey Conklin, President**