BESTBUILD LLC

86 Lonergan Dr

Suffern NY 10901

Phone: (845) 667-4980 Email: andrew@bestbld.com

PROPOSAL

Project: 1–3 South Broadway, Nyack, NY

Prepared For: *Wynnter LLC (Owner) / Kier B. Levesque, R.A. (Architect)5*

Prepared By: *BestBuild LLC*

Date:11/10/2025

SCOPE OF WORK

BestBuild LLC proposes to furnish all labor, materials, fabrication, delivery, and installation required to complete the new custom Sapele mahogany storefront and doors in accordance with approved architectural and shop drawings.

---

1. MATERIAL SUPPLY AND SHOP FABRICATION

- Supply all Sapele mahogany, marine-grade mahogany plywood, hardware, and finishing materials required for the project.
- Fabricate all storefront millwork assemblies in the shop, including vertical mullions, horizontal rails, raised panels, soffits, fascia boards, corbels, and doors.
- All joints will be glued and screwed, using miter-lock joinery where appropriate.
- Assemblies to be shop-built for precise fit, sanded, primed, and ready for installation.

2. ROUGH FRAMING

- Perform rough framing of the upper header portion of the storefront wall to establish proper height and alignment.
- This framing will provide structure for the corbels, roof system, and glass header section.

3. ROOF CONSTRUCTION

- Construct the black aluminum standing-seam roof canopy over the storefront.
- Include solid mahogany corbels, exterior paint-grade plywood infill panels, and solid mahogany soffits and fascia boards.
- Provide flashing, waterproofing, and sealant work at roof and wall transitions.

4. STOREFRONT MILLWORK INSTALLATION

- Install the solid mahogany storefront assemblies — mullions, rails, base sills, trims, and raised panels.
- Windowsills will be solid Sapele mahogany, beveled on the exterior for water drainage.
- Lower panel sections will be insulated with mineral wool, with:
    - Exterior panel: marine-grade mahogany plywood with raised molding.
    - Interior panel: ½″ finish plywood.

5. GLASS INSTALLATION

- Supply and install fourteen (14) 1″ insulated, clear tempered, low-E glass units.
- Glazing set in solid mahogany frames with removable interior stops for service access.

6. DOOR FABRICATION AND INSTALLATION

- Fabricate and install two (2) 1-3/4″ thick LVL-core Sapele mahogany doors, laminated with solid mahogany.
    - Stiles & top rail: 5½″ Bottom rail: 12″
    - Hardware: (4) Emtek NRP brass ball-bearing hinges per door, mortise lockset, lever handle, door closer.
    - Threshold: ADA-compliant aluminum (outswing).
- Includes all door hardware, locks, closers, and adjustments.
- Apartment entrance door excluded. Apartment entrance glass panel, frame, and painting included.

---

7. FINISHING AND PAINTING

- Exterior: One coat primer + two coats premium exterior-grade paint.
- Interior: One coat primer + two coats heavy-duty commercial paint.
- All concealed surfaces back-primed or/and sealed prior to installation.

CLARIFICATIONS

- Existing storefront demolition and removal excluded. The site must be clean, structurally sound, and ready for installation.
- All sales tax for materials and supplies included. Labor is tax-exempt.
- Final storefront door width = 3′-0″ (36″), verified on site.
- Shop drawings revised as needed after field measurements, then submitted for approval before fabrication.
- Lead time: ~30 calendar days from deposit and approved shop drawings.
- Minor joinery adjustments may be made for alignment and fit, without changing design intent.

EXCLUSIONS

- Demolition or removal of existing storefront.
- Electrical, lighting, signage, or unrelated work.
- Anything beyond approved shop drawings.

PAYMENT TERMS

- 30% deposit due at contract signing to secure materials and begin fabrication.
- Remaining payments follow job progress milestones.
- Upon award, a detailed payment schedule will be issued reflecting job delivery and progression.
- All invoices due upon receipt unless otherwise agreed in writing.

LUMP-SUM PROPOSAL

Total Contract Amount: $183,000.00

Includes all labor, materials, fabrication, equipment, delivery, and finishing for a complete installation.

ACCEPTANCE

Client acceptance of this proposal authorizes BestBuild LLC to proceed with procurement, shop drawings, and fabrication per these terms.

Client Signature: _____

Date: _____

Andriy Moskalyk, BestBuild LLC

Date: 11/10/2025