November 21, 2025

All Bidders:

RE: New roofing for Spark Car Wash, Newburgh NY

Dear Contractor:

It is our pleasure to provide our roofing proposal, totaling approximately 9200 SF of new roof construction, on the above-mentioned project as follows:

1) Install rooftop safety equipment per OSHA regulations prior to commencement of roofing work. All loading and un-loading of materials and equipment will be scheduled to alleviate conflict of access with other trades, to the greatest extend feasibly possible.

2) Over prepared steel roof deck, install a double-layer insulation assembly consisting of 2 layers of 2.6" thick closed cell Isocyanurate rigid foam roof insulation. Total R-value of the assembly is 30. This base insulation will be supplemented by a sloped tapered insulation system to positively divert all rainwater flow to roof drainage. Insulation layers will be protected by a single-layer of ½" thick Georgia-Pacific Dens Deck roof underlayment. All insulation panels will be tightly butted and joints staggered, mechanically fastened through all insulation layers into to the roof deck using #15 roofing fasteners and 3" diameter Rhinobond electrostatically-coated pressure-plates per manufacturer's Factory Mutual approved fastening rate. All proper perimeter and corner fastening enhancements will be added to maintain Factory Mutual 1-90 system compliance for this location's wind speed zone.

3) Install new project specified 60-mil, Sika-Sarnafil, polyester-reinforced, PVC thermoplastic roof membrane assembly over the prepared insulation layer. This new membrane will be bonded to the fastener pressure-plates by means of induction welding to the surface using roof system manufacturer's Rhinobond welding equipment. Seal all membrane panel laps using digitally controlled automatic hot air welding machines.

4) Flash all roof perimeters, roof curbs, service penetrations and drainage elements per manufacturer's recommendations, using 60-mil polyester-reinforced Sika-Sarnafil Sikaplan flashing membrane, fully adhered and terminated per manufacturer's standard details, using their prefabricated accessories to the greatest extent possible to ensure the highest quality installation.

5) Install new shop-fabricated, brake-formed from Kynar finished aluminum sheets, architectural edge metal to include new .040" thick snap-lock coping/fascia assembly, with concealed cleats, on all perimeter parapet walls detailed for such. Furnish and install matching conductor head and drop leader at high pier roof in gauge / finish to match, extended down to main roof level.

6) Provide and install surface-mounted aluminum counterflashing above horizontal membrane termination bars at rising walls, set approximately 12” above base flashing / roof tie-in

7) Provide pre-molded PVC walkway protection at roof access point

8) Completed roofing will be independently inspected by manufacturer’s field technical representative and approved installation will receive a 20-year Total System Warranty

Total Cost as Specified Above: … $ 92,570.00 (8.125-% Local NY Sales Tax on Material is Included)

Not included: Building Permits
Connection of drainage leaders to sub-surface drainage or provision of drainage adaptors
Union Labor or Prevailing Wage Rate Determined Labor (We are non-union, open shop)
Wood blocking, sheathing or other roof top carpentry.
Vapor Barriers
Dumpsters (to be provided by others for site generated debris)
Masonry & foundation waterproofing, cavity waterproofing, joint sealants and other waterproofing un-related to roofing work as specified above.
Any Off-Hours or Weekend labor for Roofing/Flashing Installation Work, unless we are using the time as a make-up for inclement weather that may occur during normal weekday business hours.
Scaffold Stair or Platform Lift Roof Access (To be provided by Others if required)
Performance and Payment Bonds (Please add 1-% of contract value if required)

Add Option: To provide and install 1-pc 2-6” x 3’-0” pre-manufactured roof access scuttle inclusive of OSHA approved perimeter safety rail assembly, please add **$3,800.00**

This Quote is Valid for Materials Delivered On-Site Thru 1st Quarter of 2026

Tecta America currently has an EMR of .51

We would be most welcome to answer any questions you may have and are looking forward to the possibility of working with you to complete this project. We are appreciative for the opportunity to provide our quotation.

Best Regards,

David J Romansky, President