Titan Mechanical NY
(845) 825-0943
90 Livingston St
Tappan, NY 10983

Prepared For	Proposal Date	Proposal Number
Steve Catalanatto Montana Contracting	10/29/2025	0000030

South Orangetown Ambulance Corps

This proposal is based off plans dated 09/09/2025

Pricing

Description	Rate	Qty	Line Total
Demo Disconnect kitchen sink, two (2) lavs, shower, two ice makers, and existing domestic cold water main in specified locations. Cap and make safe gas line feeding existing stove. Cap and make safe all water, waste and vent lines serving existing fixtures to be disconnected.	$0.00	1	$0.00
Plumbing Scope Plumbing scope to include installation of water, waste, vent, and natural gas system.	$0.00	1	$0.00
Women's Bathroom(s) Furnish and install rough plumbing to two (2) lavs, two (2) shower bases, two (2) shower valves, one (1) toilet, one (1) floor drain. At finish, install shower trim, water and waste connections to vanities (to be installed by others) , install toilet.	$0.00	1	$0.00
Men's Bathroom(s) Furnish and install rough plumbing to two (2) lavs, two (2) shower bases, two (2) shower valves, one (1) toilet, one (1) floor drain. At finish, install shower trim, water and waste connections to vanities (to be installed by others) , install toilet.	$0.00	1	$0.00
Oil Separator(s) Furnish and install three (3) Zurn 1189 100lb capacity oil separators in new truck bays.	$0.00	1	$0.00
Water Heater(s)	$0.00	1	$0.00

Furnish and install A.O. Smith BTS-199 direct vent 50 gallon water heater.			
First Floor F/I rough plumbing to one (1) kitchen sink, two (2) ice makers, shower, one (1) lav, one (1) washing machine, two (2) hose bibs	$0.00	1	$0.00
Ejector Pump(s) Furnish and install Liberty 1102/PRG101M-2 to receive fixtures in new truck bays. To tie into existing sewer line in driveway of corner of existing building.	$0.00	1	$0.00
Materials and Labor Waste piping to be ran in PVC, water lines to sink to be stubbed into sink base in copper, water lines to be ran in Type L copper with press fittings	$176,816.25	1	$176,816.25

Subtotal	176,816.25
Tax	0.00
Proposal Total (USD)	$176,816.25

Steve Catalanatto, Montana Contracting