# PROPOSAL

**Job:** CREST ROAD
**Description:** NEW HOUSE
**Location:** COLD SPRING, NY
**Client:** MONTANA
**Bid Date:** 2025-01-13
***PRICE VALID FOR 30 DAYS***
**Estimator:** KST
**Plans:** AGA, PAGE A1-002-00 (11-11-24)

| NO. | ITEM | QTY | U/M | UNIT PRICE | AMOUNT |
|---|---|---|---|---|---|
| | | | | | |
| ****THIS IS A MEMO OF UNDERSTANDING THAT THE WORK TO BE PERFORMED IS LIMITED TO THE SCOPE BELOW. THE SCOPE IS BASED SOLEY ON THE CIVIL DESIGN DRAWINGS REFERENCED ABOVE. **** | | | | | |
| | | | | | |
| 1 | MOBILIZATION | 1 | LS | $ 6,250.00 | $ 6,250.00 |
| 2 | GENERAL EXCAVATION AND GRADING AROUND HOUSE | 1 | LS | $ 49,500.00 | $ 49,500.00 |
| 3 | PREPARE ROUGH GRADE AT POOL AREA **(DOES NOT INCLUDE POOL EXCAVATION)** | 1 | LS | $ 7,500.00 | $ 7,500.00 |
| 4 | EXCAVATE FOR HOUSE FOUNDATION AND PIERS | 1 | LS | $ 15,750.00 | $ 15,750.00 |
| 5 | BACKFILL HOUSE FOUNDATION AND PIERS | 1 | LS | $ 13,500.00 | $ 13,500.00 |
| 6 | PREPARE SLAB SUB-GRADE | 1 | LS | $ 2,500.00 | $ 2,500.00 |
| 7 | FURNISH AND PLACE 6" CRUSHED STONE FOR SLAB | 1 | LS | $ 5,500.00 | $ 5,500.00 |
| 8 | FURNISH AND INSTALL FOOTING DRAINS | 300 | LF | $ 40.00 | $ 12,000.00 |
| 9 | FURNISH AND INSTALL 4" SDR-35 FROM UNDER PAVERS TO DAY LIGHT | 120 | LF | $ 50.00 | $ 6,000.00 |
| 10 | TRENCHING AND BACKFILL FOR WATER LINE **(DOES NOT INLCUDE WATER LINE PIPING)** | 500 | LF | $ 35.00 | $ 17,500.00 |
| 11 | TRENCHING AND BACKFILL FOR CONDUIT PER A1-002.00 | 850 | LF | $ 35.00 | $ 29,750.00 |
| 12 | EXCAVATE, SET AND BACKILL UNDERGROUND VAULT | 1 | LS | $ 4,500.00 | $ 4,500.00 |
| 13 | EXCAVATE AND BACKFILL FROM HOUSE TO SEPTIC TANK | 1 | LS | $ 1,500.00 | $ 1,500.00 |
| 14 | FURNISH AND INSTALL CONCRERE GENERATOR PAD | 1 | LS | $ 3,500.00 | $ 3,500.00 |
| 15 | FINE GRADE SUB-GRADE FOR PAVER DRIVEWAY AREA | 13500 | SF | $ 0.50 | $ 6,750.00 |
| 16 | FURNISH AND PLACE FILTER FABRIC UNDER CRUSHED STONE FOR PAVER AREAS | 13500 | SF | $ 0.40 | $ 5,400.00 |
| 17 | FURNISH AND PLACE 9" OF 3/4" CRUSHED STONE FOR PAVERS **(FINE GRADING OF CRUSHED STONE FOR PAVER PLACEMENT NOT INCLUDED)** | 13500 | SF | $ 3.00 | $ 40,500.00 |
| 18 | ROCK HAMMERING ALLOWANCE **($400/HR)** | 10 | DAYS | $ 3,200.00 | $ 32,000.00 |
| | | | | | |
| | | | | **TOTAL** | **$ 259,900.00** |

| ROCK REMOVAL AND UNIT PRICING | | |
|---|---|---|
| 1 | CRUSHER/EXCAVATOR/LOADER/ROCK TRUCK TO HANDLE, PROCESS OR CRUSH HAMMERED/PROCESSED ROCK | $350/HR |
| 2 | EXPORT OF EXCESS ROCK (PROCESSED OR UNPROCESSED) | $30/CY |
| 3 | EXPORT EXCESS FILL/TOPSOIL | $30/CY |
| 4 | IMPORT GENERAL FILL | $30/CY |
| 5 | IMPORT RECYCLED ITEM #4 AS STRUCTURAL FILL | $50/CY |
| 6 | SUB-SLAB TRENCHING AND BEDDDING MATERIAL (UP TO 5' DEEP) | $35/LF |
| 7 | LABORER | $100/HR |
| 8 | FIELD LEADER | $125/HR |
| 9 | EQUIPMENT AND OPERATOR | $250/HR |

| NOTES | |
|---|---|
| *1* | *THIS CONTRACT INCLUDES THE USE OF GPS 3-D MODELING OF THE SITE DESIGN AND THE USE OF GPS MACHINE CONTROL* |
| *2* | *THIS BID IS BASED SOLEY ON THE CIVIL DESIGN DRAWINGS, ANY DISCREPENCIES BETWEEN ARCHITECTURAL DRAWINGS, SPEC MANUALS, AND ANY OTHER DOCMENTATION ARE TO BE DISCUSSED AS CHANGE ORDERS* |
| *3* | *ALL QUANTITIES ARE ASSUMED TO BE LOOSE IN-TRUCK YARDS AND WILL BE TRACKED BY TRUCK LOADS @ 20 CY* |
| 4 | *ALL DIP, WATER VALVES, FITTINGS, FRAME AND GRATES/COVERS ARE PRICED AS EQUAL TO "DOMESTIC". NO "DOMESTIC" ITEMS ARE INCLUDED IN THIS PROPOSAL.* |
| 5 | *PRICING SUBJECT TO CHANGE AFTER CONTRACTS BASED ON VOLITILE MATERIAL MARKETS. THIS PRICING IS ONLY VALID FOR 30 DAYS FROM ABOVE DATE. PAST THAT MATERIAL PRICING IS SUBJECT TO REVIEW AND ADJUSTMENT* |
| 6 | *NOT RESPONSILBE FOR PUDDLING IN PAVED AREAS WITH LESS THAN 3% PITCH IN ANY DIRECTION* |

| NO. | EXCLUSIONS |
|---|---|
| 1 | CONSTRUCTION FENCING |
| 2 | ROCK REMOVAL INCLUDING HAMMERING, CRUSHING, AND ANY ASSOCIATED MACHINE TIME FOR HANDLING, EXCAVATING, CRUSHING OR LOADING OF ANY ROCK, INCLUDING HAMMERED OR PROCESSED ROCK. ROCK REMOVAL IS DEFINED AS LEDGE/BED ROCK AND/OR ANY BOULDER OVER 1 CUBIC YARD |
| 3 | DRILLING, BLASTING, SETTING OF BLASTING MATS AND ANY ASSOCIATED PERMINTS, SURVEYS, AND FEES |
| 4 | ENGINEER, SURVEYOR AND INSPECTION FEES |
| 5 | PERMITS, BONDS AND ANY ASSOCIATED FEES |
| 6 | AS-BUILTS |
| 7 | COMPACTION TESTING |
| 8 | SOIL TESTING |
| 9 | TREATMENT AND/OR REMOVAL OF UNSUITABLE SOIL DUE TO WATER CONDITION, EXCESS MOISTURE, NOT MEETING SPEC, ETC. |
| 10 | REMOVAL OF CONTAMINATED MATERIAL |
| 11 | PRIVATE MARKOUT |
| 12 | DEWATERING |
| 13 | DUST CONTROL FOR OTHERS |
| 14 | STREET CLEANING FOR OTHERS |
| 15 | MUD, SNOW AND FROST REMOVAL |
| 16 | BACKFILLING/GRADING/FILLING WITH ANY MATERIAL OTHER THAN ON-SITE EXCAVATED MATERIAL AND, EXPORT OF EXCESS FILL IF GENERATED, AND IMPORT OF SELECT STRUCTURAL FILL. ASSUMED TO **ONLY** USE ON-SITE MATERIAL FOR ALL CUTS/FILLS/GRADING/BACKFILLING/ETC. |
| 17 | MOVING AND HANDLING OF MATERIAL FROM OTHER TRADES TO ALLOW FOR SITE WORK TO CONTINUE |
| 18 | LEADER DRAIN LAYOUT- LAYOUT TO BE MARKED ON FOUNDATION BY OWNER/GC |
| 19 | BRINGING ANY UTILITIES INTO BUILDING - ASSUMED ALL TERMINATE 5' OUTSIDE FOUNDATIONS |
| 20 | IMPORT/EXPORT OF TOPSOIL, FILL OR ROCK |
| 21 | RAKING, SEEDING AND LANDSCAPING |
| 22 | RE-SPREADING OF TOPSOIL |
| 23 | FENCING, GATES, GUIDE RAILS, RAILINGS, ETC. |
| 24 | NOT RESPONSIBLE FOR FROST HEAVING |
| 25 | NOT RESPONSIBLE FOR STANDING WATER IN PAVEMENT AREAS WITH LESS THAN 3% PITCH IN ANY DIRECTION |
| 26 | SEPTIC TANKS AND PIPING |
| 27 | WATER LINE PIPING |
| 28 | POOL AND POOL DECK EXCAVATION AND FINE GRADING/PREP |
| 29 | SUB-SLAB TRENCHING |
| 30 | PAVERS |
| 31 | SILT FENCE AND EROSION CONTROL |
| 32 | ANY WORK OUTSIDE OF A1-002.00 |
| 33 | PATHS AND WALKWAYS AND ANY ASSOCIATED PREP |
| 34 | WEED, BRUSH, LOG, DERBIS, ETC. REMOVAL AND HANDLING |

| | | | |
|---|---|---|---|
| **SUBMITTED BY:** KEVIN TOMPKINS | *Kevin Tompkins* | | |
| | | **DATE:** | 1/13/2025 |

| | | | |
|---|---|---|---|
| **ACCEPTED BY:** | | | |
| | | **DATE:** | |