VISLOCKY PAINTING
Commercial and Industrial Painting
300 New Hempstead Rd New City, NY 845-638-1403

PROPOSAL

DATE: 9/9/2025
TO: Montana Contracting
Attn: J Montana / Project Management
RE: **Big Geyser Warehouse – Brewster NY**

Description Of Work To Be Performed:

Vislocky Painting to Provide all Labor and Supervision in accordance with request from Montana CC personnel per walkthroughs 8/20/25 and 8/27/25

Exterior Powerwashing

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access.
2. Pressure cleaning of all exterior surfaces to be painted (Roofing, Gutters, Leaders, Soffits, Metal Wall Panels With Aggregate, Metal Wall Panels Without Aggregate, Stucco/EIFS Accent Columns, Metal Window and Door Frames etc.
3. Painted Metal Roofing and Metal Siding to receive T,S,P solution cleaner to assist with adhesion of to be installed coatings
4. Per request from Benjamin Moore reps, all surfaces are to be "clean dull and dry" prior to application of finish coatings

Powerwashing Work For The Sum Of
($7,000.00) Dollars

Exterior Siding and Windows Phase 1 (Fall 2025)

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access
2. Protection of adjacent, not to be painted, surfaces. Including but not limited to, Windows, Floors, Walkways etc.
3. No priming required for previously coated surfaces (per Benjamin Moore Rep)
4. Application of 2 coats Benjamin Moore Ultra Spec Elastomeric Waterproof Coating to all Stucco/EIFS Wall Surfaces. (Front of Building) Including Main Entry Area-Center Section and Front Of Building EIFS Pilasters. NOT Including Metal Siding With Textured EIFS finish
5. Application of 2 coats Benjamin Moore Ultra Spec HP DTM to all Previously Painted Exterior Metal Window Frames and Hollow Metal Doors and Frames in Front of Building and Main Entry-Center Section as indicated

Exterior Siding and Windows Phase 1 Work For The Sum Of
($40,000.00) Dollars

Exterior Siding and Windows Phase 2 (Spring 2026)

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access
2. Protection of adjacent, not to be painted, surfaces. Including but not limited to, Windows, Floors, Walkways etc.
3. No priming required for previously coated surfaces (per Benjamin Moore Rep)
4. Application of 2 coats Benjamin Moore Ultra Spec Elastomeric Waterproof Coating to all remaing Metal Siding With Textured EIFS finish (front of Building
5. Application of 2 coats Benjamin Moore Ultra Spec HP DTM to all Exterior Previously Painted Metal Siding Wall Surfaces. (Back of Building)
6. Application of 2 coats Benjamin Moore Ultra Spec HP DTM to all Previously Painted Exterior Metal Window Frames and Hollow Metal Doors and Frames (Not Painted in Phase 1)
7. Phase 2 **DOES NOT** include repainting of areas/locations previously painted in Phase 1

Exterior Siding and Windows Phase 2 Work For The Sum Of
($40,000.00) Dollars

Roof Coating

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access
2. Protection of adjacent "not to be painted" surfaces. Including but not limited to, Windows, Floors, Walkways etc.
3. No priming required for previously coated surfaces (per Benjamin Moore Rep)
4. Spray Application of 1 coat Benjamin Moore Etching Primer (To Be Determined) and 2 Coats of " Faster Curing 2 Component Product" (To be determined) to all Standing Seam Metal Roofing, Rain Gutters and Gutter Leader Surfaces
5. **PLEASE CONSIDER THIS AS BUDGET PRICING, AS WE HAVE NOT CONFIRMED THE COATING SYSTEM**

Roof Coating Work For The Sum Of
($72,000.00) Dollars

Interior Proposed Warehouse Beams and Struts

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access
2. Protection of adjacent "not to be painted" surfaces. Finished Walls at Columns etc. As described in noted provided
3. No priming required for previously coated surfaces (per Benjamin Moore Rep)
4. Application of 2 coats Benjamin Moore DTM HP DTM to all Beams and diagonal bracing "struts" in 2 Warehouses (Approximately 20 beams)

Warehouse Beams Work For The Sum Of
($17,000.00) Dollars

Interior Proposed Warehouse Purlins

1. Furnish and Use of required Man Lifts (Booms/Scissors) for high reach access
2. NO Protection of adjacent "not to be painted" surfaces. Including but not limited to, Windows, Floors, Walkways etc. as all surfaces in this area are to be demolished
3. No priming required for previously coated surfaces (per Benjamin Moore Rep)
4. Application of 2 coats Benjamin Moore DTM HP DTM to all cross Purlins between beams in 2 Warehouses
5. Application of 2 coats Benjamin Moore DTM HP DTM to all X Braces (Rod Bracing) between beams in 2 Warehouses

Warehouse Purlins Work For The Sum Of
($20,000.00) Dollars

ALL Warehouse Beams, Purlins and X Braces at one time

1. NO Protection of adjacent "not to be painted" surfaces. Including but not limited to, Windows, Floors, Walkways etc. as all surfaces in this area are to be demolished
2. Cost for finishing of Warehouse Beams, Purlins and All X Braces etc, if done at one time in 1 color in both warehouses

($5,000 discount for single mobilization)
Combined Warehouse Work For The Sum Of
($32,000.00) Dollars

Interior Proposed Office Space

1. Furnish and Use of required Man Lifts (Booms/Scissors) or Scaffolding, Ladders etc. for high reach access
2. Standard Interior Painting of new and existing drywall surfaces (Walls, Soffits Ceilings) all required Offices, Common Areas, Hallways Rest Rooms, Conference Rooms Etc.
3. Finish Painting of all required new and existing Hollow Metal Doors and Frames. Hollow Metal Window and Window Frames. Etc
4. This quote does not include any finishes to exposed ceilings, ornate high reach type soffit work, faux finishes or wallcoverings etc.
5. Quote is to be considered a "budget price" for evaluation purposes. We have not seen drawings, finish schedules etc.

Interior Office Space Work For a BUDGET Sum Of
($42,000.00) Dollars

Exclusions and/or Qualifications:

- All work to be performed in one phase during normal working hours 7am to 4pm.
- Quote does not include furnish/purchase of any paint materials. As directed by Benjamin Moore Reps. All materials to be purchased directly by Big Geyser. Quantities and Costs TBD by Benjamin Moore or others
- Equipment, Brushes, Rollers, Masking Materials etc. are included in labor pricing
- This quote does not include Treatment/Caulking/Sealing of any kind to fasteners on Roofing surface. Per Montana Contracting, all Roofing Screws/Fasteners are to be replaced prior to paint installation.

ALL Work For The Sum Of
($220,000.00) Dollars