Zold Electric Inc

Lic. #: WC# 1968, PC#10328
226 Tibet Drive
Carmel, NY 10512

(845) 306-7529
joe.bene@zoldelectric.com
www.zoldelectric.com

Proposal

Proposal Number: **P-1705**
Proposal Date: Dec 17, 2024
Proposal Expires: Jan 16, 2025

Client

Montana Contracting - Congers (Ines MacAdam)
173 US-9W
Congers, NY 10920
(845) 398-1778
a.divernieri@montanacontracting.com

Billing Address

Project

1705 - Crest Road
Crest Road
Philipstown, NY 10516

Thank you for inviting us to provide you an estimate for your project. Please review the proposed scope of work and let us know if you have any questions.

DESCRIPTION	PRICE
Residential Bid	$136,921.63
Labor SOW	
Commercial Project Total Labor	*$67,375.00*
**scope of work	
• Install new NEMA1R 600Amp 1PH Switchboard/MDP to specifications on single line diagram per engineer sheet plan	

- Install Metering System per metered space required per single line diagram. CT cabinets will be external of Switchboard
- Install new 600amp service from Electrical room to utility manhole box for pad mount transformer vault. 2 sets of 350 KCMIL THHN CU will be installed for service secondary's with properly sized Grounding.
- install primary high voltage conduits and cables from transformer vault to nearest utility pole with 3phase primary set.
- installation of hand hole boxes where required for pull on site drawings
- install all new power and lighting circuits called on drawings for drawing sets
- install all receptacles on drawings specified with rating of application
- install all lighting from fixture schedule on lighting drawings specified by lighting schedule at intended locations. Fixtures are budgeted in package as similar to specifications due to lack of MFG detail
- lighting/power circuits to be routed close to beams on exposed ceiling areas via EMT conduit where applicable
- All trenching for underground electrical conduits shall be done by others

Demo Stage

- N/A

Site Conduit Work

- All conduits installed below grade noted on site plan
- All conduits installed for preparation of landscape/site lighting work per plan layout on
- Handholes where needed for deck lighting boxes
- Conduits for Service entrance and primary utility lines

Temporary Service for site work

- Install temporary 120/208v 3PH 200amp NEMA3R underground service
- Install one 120/208v 3PH 200amp NEMA3R 30ckt Panelboards
- Install 6- 20amp 120v GFCI protected circuits with duplex receptacles and nema3r covers.

Power Circuits Work

- Power to all EDH units

- Power to EF-R units
- Power to all FCU units
- Power to all CU units
- Power to HWH unit
- Power to Steamer units
- power to floor heating units
- Power to all EF units
- Power to TX-A bathroom exhaust
- Power to Sub Pump system
- power and controls to sewage ejector system
- Duplex outlets where allocated per power power plans
- Duplex outlets - GFI (WP) where allocated per power power plans
- Quad Duplex outlets
- Duplex outlets - (240V) rated
- Junction Box - various
- Power to all kitchen appliances/circuits per power plan layout.
- Floor receptacles and data housings
- install smoke/CO detector system throughout dwelling per code requirements.

**all feeder power circuits for equipment above 20amps to have local disconnects within sight of equipment by 2017 NEC code.

Pool Electrical Work

- install all circuitry and controls for pool lighting
- install receptacles per pool drawings
- install power to all pump/control/valves/equipment for pool
- install equipotential grounding system for pool
- install lighting and power for jacuzzi

Lighting circuit Work

- Dual Occupancy/vacancy Sensor controls to installed via ceiling mounted
- Occupancy Grouped lighting per lighting plan
- Single pole Switch to allocated lighting circuits that are designed to be switched in single location per lighting plan layout.

- Single 3-way Switch to allocated lighting circuits that are designed to be switched in multiple locations per lighting plan layout.
- Occupancy & Vacancy Sensors per lighting plan layout per their assigned lighting runs.
- Install all assigned fixtures per fixture schedules for all designated locations on lighting plan.
- Install all site/exterior lighting per lighting plan layout.

Switchboard & Panelboard Work

- Install 600Amp NEMA1R service entrance rated CT cabinet accessibly by CENTRAL HUDSON utility for 120/240v 1ph secondary service
- install 600amp NEMA1R 1PH 120/240v 62KAIC rated MDP Switchboard for incoming utility 120/240v secondary service.
- install 1PH 120/240v 150amp MLO 1PH NEMA1R Panelboard RPA
- install 1PH 120/240v 150amp MLO 1PH NEMA1R Panelboard RPB
- install 1PH 120/240v 225amp MLO 1PH NEMA1R Panelboard POOL

Utility Work

- Install Pad mount transformer pad & Vault near utility location to house utility supplied pad mount transformer.
- Transformer and Utility installation fee to be paid by others
- Vault & Pad mount size will be determined after utility Load letter has been submitted and field planner has determined suitable transformer size.
- Install conduit from vault to nearest utility pole with 1phase primary for 14.5KV primary MV-90 cable
- install one set of 14.5KV primary MV-90 cables from vault to pole for utility company to install onto primary distribution taps
- install 2 sets of 3 wire 350KCMIL CU THHN from vault to End box CT cabinet within conduit

Labor rates & markups

Journeyman Labor Rates :

- Regular $95.00
- Overtime $118.50

- Emergency $142.50

Helper Labor Rates :

- Regular $45.00
- Overtime $67.50
- Emergency $112.50

Service Calls:

Regular Business Hours Monday-Friday 7:30-4:00

- Regular $186.00
- Overtime $233.25
- Emergency $279.00

Rentals:

- Scissor Lift (20ft Vertical) $655.00 *weekly*
- Boom Lift (50'ft) $1,250 *weekly*

Additional Fees:

- SWIS - Inspectors Consultation Fee (3rd party) $125.00
- Disposal $500.00

Material markups

- all material markups range from 10-20% depending on order size

Notes

**All HVAC equipment, i.e..; heaters/control systems/blowers shall be furnished by HVAC contractor or others.

**All Plumbing equipment and related controls will be supplied by others.

**All trenching for electrical conduits to be done by others

**project will NY tax Exempt for capital improvement

Materials	
Permitting and Inspections	*$67,462.38*
Putnam County Electrical Permit *$2,084.25* • Filing of Putnam County Electrical Permit SWIS - Residential Inspection 4000-6999sqft 4000-6999 Square Feet: Billed on Sq. Footage of Renovation. May Include up to 4 Visits (Services Inspection, if Needed Will Be Included in the 4 Visits.) SWIS - Commercial Service Inspection 201-800 AMP Service Inspection Fee - Commercial (201-800amp)	
Switchgear & Panelboards Package	$23,111.00
Switchgear & Panelboards Electrical Gear Package (Eaton, MFG.) • 600Amp 120/240v 1ph MDP • RPA panel • RPB panel • 600amp Main disconnect 1ph NEMA3R breaker type/fused • 600amp 1ph CT cabinet central Hudson utility • Surge Protective Device, Medium Exposure, TME277Y100WM Marks: 200KA SPD • Switches and Disconnects, Heavy Duty Safety Switch, TH4363 Marks: 100AMP DISCONNECT • Switches and Disconnects, Heavy Duty Safety Switch, TH4362 Marks: 60AMP DISCONNECT • Switches and Disconnects, Heavy Duty Safety Switch, TH3364R Marks: 600AMP 3R DISCON	

• Switches and Disconnects, Heavy Duty Safety Switch, TH3362R Marks: 60AMP 3R DISCON • Switches and Disconnects, Heavy Duty Safety Switch, TH3361R Marks: 30A 3R DISCON *All Power Panel Boards to be 10-42KAIC rated *All Switchboards to be 42KAIC rated at a minimum **Main Switchboard and all metering related equipment shall be designed for utility specifications. • All Panelboards were quoted with copper bus. • Fuses for all Disconnects were included in price. Lead times as follows • Main Switchboard = 120 working days • CT meters = 20-40 workings days • Panelboards = 80 Working Days • Disconnects = 20 working days	
Lighting Package Budget <u>Fixture Package</u> Fixture Package Counts and Types (budget package amount) • lighting package and control scheme missing from drawings and fixture schedule. budget allowance has been put in place for buying out total lighting/control package.	$57,608.40
Low Voltage System <u>Commercial Project Total Labor</u> **scope of work	$22,925.08

*new installation of Low voltage structured cabling for following systems • access keypads conduits for OSC • cameras • monitors for camera system • DVR • alarm system • installation of data/telephone cables with appropriate jacks per location • security rack for all data/security equipment • installation of conduit sleeves down surface mount walls for LV cables *commissioning and termination of security system/AV system to be done by OSC	
Industrial Generator <u>Industrial Generator Package</u> Industrial Kohler Generator Package from Zold Electric as follows: Generator • 125KW • 120/240V • 1PH 2Pole • LPG • 500Amp MCB • 9L,V-type8-Cylinder,Tubrocharged&Aftercooled ATS • 600Amp MCB • 120/240v • 1ph • smart AC load shed module control *crane service for installation and setting	$49,450.00

Floor Heating <u>Nuheat Floor heat Package</u> Floor Heating Package Custom Mesh Mats as follows • gym basement 100sqft qty.1 • Master bedroom 87sqft qty.1 • master bedroom 14sqft qty.1 • master bathroom 20sqft qty.1 • bedroom-2 35sqft qty.1 • bedroom-3 35sqft qty.1 • bedroom-4 35sqft qty.1 • bathroom 15sqft qty.1 • living rm 180sqft qty.1 • kitchen 30sqft qty.1 • hallway bath 20sqft qty.1 • 1st floor room 18sqft qty.1 • home office 42 sqft qty.1 • mud room 38sqft qty.1 <u>Nuheat WiFi Tstat</u> Nuheat SIGNATURE Programmable WiFi Thermostat AC0055	$18,999.03
Pool Electrical Work <u>Project Total Labor</u> **scope of work *new install • installation of new pool feeder from MDP to pool panel • install pool panel feeder in pool equipment location • install conduits for pool equipment and all underground pool lights and area power/lighting • wire all equipment to manufacturers specs. • all pool related equipment to be furnished by others and wired by zold electric • provide grounding and bonding for pool equipment and equipotential bonding ring	$11,034.70

PVC 2" CONDUIT SCH40

PVC 2-IN SCH 40 CONDUIT

1/0 AWG THHN-BLK-CU

WIRE THHN-1/0-BLK-19STR-CU

PVC 3/4" CONDUIT SCH40

PVC 3/4 inch Schedule 40 CONDUIT

12AWG THHN-BLACK-STR

WIRE THHN-12-BLACK-STR-CU-500SP

RESI Material

SOUTHWIRE Bare Copper Grounding Wire: Bare Copper Grounding Wire, 8 AWG Wire Size, Solid, 500 ft Lg

Metal Enclosure

- 6"x6"x24" Trough
- UL870 Type 1
- cUL Type 1
- Complies with
  - NEMA Type 3R
  - IEC 60529, IP20

Service/Distribution Equipment

Cutler Hammer Eaton 200Amp single phase NEMA3R outdoor Main circuit breaker 30/60 space Load Center

PVC 3/4" EXP CPLG

3/4 in. Schedule 40 and 80 PVC Standard Expansion Coupling

Pool Equipment

Pool-Spa Junction Box - 4 Light Capacity Water Tight Outdoor Grade Plastic - Intermatic PJB4175

WR GFCI Outlet

15 Amp 125-Volt Duplex Self-Test Tamper Resistant/Weather Resistant GFCI Outlet, White	
Subtotal	$320,049.84
Taxable Subtotal	$0.00
Tax 8.375%	$0.00
Total	**$320,049.84**

Electrical Services Agreement

Zold Electric Inc. & General Contractor

For the purpose of this document the General Contractor listed in Proposal as Client shall be the referred to as client in this document.

For the Purpose of this document Zold Electric Inc shall be listed as the Contractor in reference to this document.

This Electrical Services Agreement is made between **Zold Electric Inc.,** 226 Tibet Drive, Carmel, NY 10512 and Client at (specified billing address in Proposal).

This agreement is made affective as of the date of electronically signed/approval of this Proposal.

The Contractor desires to provide Electrical services to The Client and The Client desires to obtain such services from The Contractor.

THEREFORE, in consideration of the mutual promises set forth below, the parties agree as follows:

DESCRIPTION OF SERVICES: Zold Electric Inc. will provide Client electrical services and/or electrical repairs at the *property listed above*. Specifically, The Contractor shall provide:

The following electrical services stated above and any approved and signed change orders.

SCOPE OF WORK: The Contractor shall provide all labor and materials and perform all work necessary for the completion of the Electrical Services as described above.

PAYMENT: The Payment shall be made to ***Zold Electric Inc., 226 Tibet Drive, Carmel, New York 10512.***

Client agrees to pay the sum provided in each proposal:

Event:	Payment Amount:
Deposit	10% Total
Progress Payments (AIA) documents with NET30 payments.	Payment requisitions shall be made per progress of project with AIA
Final Completion	10% retainage ,final total, in addition to any change orders

Given other payment arrangements are not stated in the contract

If any invoice is not paid when due, interest will be added to and payable on all overdue amounts at 15 percent per year, or the maximum percentage allowed under applicable laws, whichever is less. The Client shall pay all costs of collection, including without limitation, reasonable attorney fees.

In addition to any other right or remedy provided by law, if the Client fails to pay for the Services when due, **Zold Electric Inc.,** has the option to treat such failure to pay as a material breach of this Agreement, and may cancel this Agreement and/or seek legal remedies.

PERMITS: The Contractor shall apply for and obtain such permits and regulatory approvals as may be required by the local municipal/county government; the cost thereof shall be included as part of Payment to the Contractor under this Agreement.

INSURANCE: The Contractor shall maintain general liability, workers compensation and builder's risk insurance.

SURVEY AND TITLE: The Owner/Client will indicate the property lines to the Contractor and will provide boundary stakes by a licensed land surveyor if the Owners are in doubt about the property boundaries.

ACCESS: The Owner will allow free access to work areas for workers and vehicles and will allow areas for the storage of materials and debris. Driveways will be kept clear for the movement of vehicles during work hours. The Contractor will make reasonable efforts to protect driveways, lawns, shrubs, and other vegetation.

FINAL INSPECTIONS AND LIENS: Upon notification by The Contractor of substantial completion of the work, The Owner/Client and The Contractor shall inspect the work performed and shall identify any incomplete work or deficiencies in workmanship or materials. When The Owner/Client finds the work is completed, The Owner/Client shall pay The Contractor any balance of the Payments to The Contractor. Upon receiving the payment, The Contractor shall deliver The Owner a release of all liens.

WARRANTY: Zold Electric Inc., shall provide its services and meet its obligations under this Agreement in a timely and workmanlike manner, using knowledge and recommendations for performing the services which meet generally acceptable standards in Zold Electric Inc.'s, community, and region, and will provide a standard of care equal to, or superior to, care used by contractors similar to Zold Electric Inc., on similar projects.

COMPLETION OF SERVICES: Upon the completion of the Electrical services by The Contractor, The Contractor shall see to it that The Owner's property is restored to the condition they were in prior to the entry by The Contractor, and The Contractor shall see to it that all portions used by The Contractor during the term of this Agreement shall be broom clean and free of debris.

DEFAULT: The occurrence of any of the following shall constitute a material default under this Agreement:

a. The failure to make the required payment when due.

b. The insolvency or bankruptcy of either party.

c. The subjection of any of either party's property to any levy, seizure, general assignment for the benefit

of creditors, application or sale for or by any creditor or government agency.

d. The failure to make available or deliver the Services in the time and manner provided for in this Agreement.

REMEDIES: In addition to any and all other rights a party may have available according to law, if a party defaults by failing to substantially perform any provision, term or condition of this Agreement (including without limitation the failure to make a monetary payment when due), the other party may terminate the Agreement by providing written notice to the defaulting party. This notice shall describe in sufficient detail the nature of the default. The party receiving such notice shall have 30 days from the effective date of such notice to cure the default(s). Unless waived by a party providing notice, the failure to cure the default(s) within such a time period shall result in the automatic termination of this Agreement.

FORCE MAJEURE: If performance of this Agreement or any obligation under this Agreement is prevented, restricted, or interfered with by causes beyond either party's reasonable control ("Force Majeure"), and if the party unable to carry out its obligations gives the other party prompt written notice of such event, then the obligations of the party invoking this provision shall be suspended to the extent necessary by such event. The term Force Majeure shall include, without limitation, acts of God, plague, epidemic, pandemic, outbreaks of infectious disease or any other public health crisis, including quarantine or other employee restrictions, fire, explosion, vandalism, storm or other similar occurrence, orders or acts of military or civil authority, or by national emergencies, insurrections, riots, or wars, or strikes, lockouts, work stoppages, or supplier failures. The excused party shall use reasonable efforts under the circumstances to avoid or remove such causes of non-performance and shall proceed to perform with reasonable dispatch whenever such causes are removed or ceased. An act or omission shall be deemed within the reasonable control of a party if committed, omitted, or caused by such party, or its employees, officers, agents, or affiliates.

ARBITRATION: Any controversies or disputes arising out of or relating to this Agreement shall be resolved by binding arbitration in accordance with the then-current Commercial Arbitration Rules of the American Arbitration Association. The parties shall select a mutually acceptable arbitrator knowledgeable about issues relating to the subject matter of this Agreement. In the event the parties are unable to agree to such a selection, each party will select an arbitrator and the two arbitrators in turn shall select a third arbitrator, all three of whom shall preside jointly over the matter. The arbitration shall take place at a location that is reasonably centrally located between the parties, or otherwise mutually agreed upon by the parties. All documents, materials, and information in the possession of each party that are in any way relevant to the dispute shall be made available to the other party for review and copying no later than 30 days after the notice of arbitration is served. The arbitrator(s) shall not have the

authority to modify any provision of this Agreement or to award punitive damages. The arbitrator(s) shall have the power to issue mandatory orders and restraint orders in connection with the arbitration. The decision rendered by the arbitrator(s) shall be final and binding on the parties, and judgment may be entered in conformity with the decision in any court having jurisdiction. The agreement to arbitration shall be specifically enforceable under the prevailing arbitration law. During the continuance of any arbitration proceeding, the parties shall continue to perform their respective obligations under this Agreement.

ENTIRE AGREEMENT: This Agreement contains the entire agreement of the parties, and there are no other promises or conditions in any other agreement whether oral or written concerning the subject matter of this Agreement. This Agreement supersedes any prior written or oral agreements between the parties.

SEVERABILITY: If any provision of this Agreement will be held to be invalid or unenforceable for any reason, the remaining provisions will continue to be valid and enforceable. If a court finds that any provision of this Agreement is invalid or unenforceable, but that by limiting such provision it would become valid and enforceable, then such provision will be deemed to be written, construed, and enforced as so limited.

AMENDMENT: This Agreement may be modified or amended in writing, if the writing is signed by the party obligated under the amendment.

GOVERNING LAW: This Agreement shall be construed in accordance with the laws of the State of New York.

NOTICE: Any notice or communication required or permitted under this Agreement shall be sufficiently given if delivered in person or by certified mail, return receipt requested, to the address set forth in the opening paragraph or to such other address as one party may have furnished to the other in writing.

WAIVER OF CONTRACTUAL RIGHT: The failure of either party to enforce any provision of this Agreement shall not be construed as a waiver or limitation of that party's right to subsequently enforce and compel strict compliance with every provision of this Agreement.

Disclaimer:

Zold Electric Inc. is NOT responsible for existing wiring conditions in buildings/ existing code violations/ building permit fees/electrical fixtures supplied by owner/ repairs to interior and exterior furnished walls due to electrical work and repairs due to unforeseen conditions. Electrical Projects WITHOUT engineered electrical drawings stamped by the Authority Having Jurisdiction (AHJ) or any type of blueprint/schematic with engineered seals, **Zold Electric Inc.,** will NOT be held responsible for additional work due to incomplete drawings and will be wired to current NEC code cycle as a minimum standard. All additional work will be considered a Change Order/Extra work order. All deposits are non-refundable.

Disclaimer for Suppliers:

- Due to global resources, workforce limitations, price escalations and raw commodities volatility this quote is valid for 30 days or the next price increase whichever occurs first.
- Supplier shall not be responsible for any failure to perform, or delay in performance of, its obligations resulting from the COVID-19 pandemic or any future epidemic, and Buyer shall not be entitled to any damages resulting thereof.