CREATED DATE
1/27/2025

LATEST UPDATE
2/10/2025

OWNER
Kevin Gribbon

SOLD BY:

Blue Ridge Lumber Fair Lawn
12 Jacksonburg Rd
Blairstown, NJ 07825-9615

SOLD TO:

,

Abbreviated Quote Report - Customer Pricing

QUOTE NAME	PROJECT NAME	QUOTE NUMBER	CUSTOMER PO#	TRADE ID
Montana Cont.	5 Heidi Ln	7002430		

ORDER NOTES:	DELIVERY NOTES:



Item	Qty	Operation	Location	Unit Price	Ext. Price
100	**1**	**Stationary-Stationary-Right**	**001**	**$6,616.15**	**$6,616.15**

RO Size: 110" x 84 1/2" **Unit Size: 109 1/4" x 84"**

Mull: Job Site Mulled, Field Ribbon Mull, 2 inch Support Mullion Material
FWG 3'X7'-FWG 5' 11 1/4"X7', Unit, Unit 1: 400 Series Patio Doors 1 Panel-FWG, Unit 2: 400 Series Patio Doors 2 Panel-FWG, Factory Assembled, White Exterior Frame, White Exterior Sash/Panel, Pine w/White Interior Frame, Pine w/White Interior Sash/Panel, Unit 1: Stationary, Unit 2: Stationary-Right, Dual Pane Low-E4 Tempered Series Argon Fill Stainless Glass / Grille Spacer, Tribeca, White, White, Exterior Keyed Lock, Lock Cylinder Keyed Alike, White, Full Screen, Fiberglass, Gliding
Wrapping: 6 9/16" Interior Extension Jamb Pine / White - Painted Standard Individual Units (Boxed) Complete Unit Extension Jambs, Job Site Applied

FWG 3'X7'-FWG 5' 11 1/4"X7', Unit, 400 Series Patio Doors 1 Panel-FWG, Factory Assembled, White Exterior Frame, White Exterior Sash/Panel, Pine w/White Interior Frame, Pine w/White Interior Sash/Panel, Stationary, Dual Pane Low-E4 Tempered Series Argon Fill Stainless Glass / Grille Spacer

FWG 3'X7'-FWG 5' 11 1/4"X7', Unit, 400 Series Patio Doors 2 Panel-FWG, Factory Assembled, White Exterior Frame, White Exterior Sash/Panel, Pine w/White Interior Frame, Pine w/White Interior Sash/Panel, Stationary-Right, Dual Pane Low-E4 Tempered Argon Fill Stainless Glass / Grille Spacer, Tribeca, White, White, Exterior Keyed Lock, Lock Cylinder Keyed Alike, White, Full Screen, Fiberglass, Gliding

GD33, EXT JAMB, HEAD KIT 6 9/16 WALL PAINTED WHITE INT PN:2567332

GD80, EXT JAMB, SIDE KIT 6 9/16 WALL PR PAINTED WHITE INT PN:2567378

Trim Set 1: FWG Stationary-Right Tribeca White PN:2565694

Auxiliary Foot Lock 1: FWG White PN:1997301

Exterior Keyed Lock - Keyed Alike 1: FWG RH Tribeca White PN:9056180

Insect Screen 1: 400 Series Patio Doors 2 Panel-FWG, FWG 71.25 x 84 Full Screen Fiberglass Gliding White

GD60, EXT JAMB, HEAD KIT 6 9/16 WALL PAINTED WHITE INT PN:2567335

GD80, EXT JAMB, SIDE KIT 6 9/16 WALL PR PAINTED WHITE INT PN:2567378

Drip Cap: 120IN White QTY 1 PN:2222546

Join Mull Material: 400 Series Patio Doors FWG, 95.5, Vertical 2 inch Support Mullion White, Pine, White, PN:2510214

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.3	0.26	NO
B1	0.3	0.26	



Item	Qty	Operation	Location	Unit Price	Ext. Price
200	**1**	**Fixed-Fixed**	**002**	**$3,123.83**	**$3,123.83**

RO Size: 96 1/2" x 84 1/2" **Unit Size: 96" x 84"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
SCA 3' 11 3/4"X7'-SCA 3' 11 3/4"X7', Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 4 9/16" One Piece Step Jamb Vertical Grain Douglas Fir / Unfinished Individual Units (Boxed) Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.33	NO
B1	0.29	0.33	



Item	Qty	Operation	Location	Unit Price	Ext. Price
300	**1**	**Right**	**101**	**$7,575.61**	**$7,575.61**

RO Size: 42 5/8" x 114 1/2" **Unit Size: 42" x 114"**

AEOD 3' 6"X9' 6", Unit, Architectural Entry Doors 1 Panel Residential Outswing, 196 Panel, Standard Panel Layout, 4 9/16" Frame Depth, Bronze - Painted On-Floor Drainage Sill, 5 3/8" Stile Width, 6 3/8" Top Rail Height, 9 5/8" Bottom Rail Height, Oak w/Unfinished Exterior Frame, Oak w/Unfinished Exterior Sash/Panel, Oak w/Unfinished Interior Frame, Oak w/Unfinished Interior Sash/Panel, Right, Satin Nickel
Wrapping: 6 9/16" Interior Extension Jamb Oak / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	---	---	NO	A1	37.4080	111.159	28.8766



Item	Qty	Operation	Location	Unit Price	Ext. Price
400	**1**	**Fixed**	**102**	**$1,682.85**	**$1,682.85**

RO Size: 32 1/2" x 114 1/2" **Unit Size: 32" x 114"**

SCA 2' 8"X9' 6", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.32	NO



Item	Qty	Operation	Location	Unit Price	Ext. Price
500	**1**	**Fixed**	**103**	**$1,825.40**	**$1,825.40**

RO Size: 44 1/2" x 114 1/2" **Unit Size: 44" x 114"**

SCA 3' 8"X9' 6", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.32	NO



Item	Qty	Operation	Location	Unit Price	Ext. Price
600	**1**	**Fixed-Right**	**106**	**$2,390.12**	**$2,390.12**

RO Size: 85" x 58 1/2" **Unit Size: 84 1/2" x 58"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
SCA 5'X4' 10"-CAX 2'X4' 10", Unit, Unit 1: E-Series Picture Window, Unit 2: E-Series Casement, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Fixed, Unit 2: Right, Direct Set (1 Piece), Align w/Stationary Stops, Standard Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Insect Screen 1: E-Series Casement, CAX 24 x 58 Full Fiberglass White

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.29	0.33	NO	B1	15.8125	53.3125	5.85420
B1	0.3	0.29					



Item	Qty	Operation	Location	Unit Price	Ext. Price
700	**1**	**Fixed - Right - Fixed**	**107**	**$5,354.14**	**$5,354.14**

RO Size: 70 3/4" x 90 1/2" **Unit Size: 70 1/4" x 90"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
ADGS 1' 4 3/8"X7' 6" - AFDI 3' 1/2"X7' 6" - ADGS 1' 4 3/8"X7' 6", Unit, Unit 1, 3: E-Series Inswing Door Sidelight-Contemporary, Unit 2: E-Series Inswing Door-1 Panel-Contemporary, Standard Panel, 6 9/16" Frame Depth, Factory Assembled, Exterior Trim Installation Flange, Direct Set, Clear Anodized Unit 1, 3: On-Floor Sill, Unit 2: On-Floor Drainage Sill, 3 11/16" Stile Width, 3 11/16" Top Rail Height, 3 11/16" Bottom Rail Height, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1, 3: Fixed, Unit 2: Right, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, White
Wrapping: 2" Ovolo Brickmould 3-Sided White 2604 Factory Applied Exterior Trim

Mull Cover: ADGS, 96IN, Vertical Grain Douglas Fir, Unfinished, PN:9084781
Mull Cover: AFDI, 96IN, Vertical Grain Douglas Fir, Unfinished, PN:9084781

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	---	---	NO	B1	32.0000	86.3750	19.1944
B1	0.31	0.28					
C1	---	---					



Item	Qty	Operation	Location	Unit Price	Ext. Price
800	**1**	**Fixed**	**108**	**$742.33**	**$742.33**

RO Size: 36 1/2" x 36 1/2" **Unit Size: 36" x 36"**

SCA3030, Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.33	NO



Item	Qty	Operation	Location	Unit Price	Ext. Price
900	**1**	**Left-Fixed**	**110**	**$2,375.59**	**$2,375.59**

RO Size: 85" x 66 1/2" **Unit Size: 84 1/2" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
CAX2656-SCA4656, Unit, Unit 1: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Standard Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Insect Screen 1: E-Series Casement, CAX2656 Full Fiberglass White

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	21.8125	61.3125	9.28740
B1	0.29	0.33					



Item	Qty	Operation	Location	Unit Price	Ext. Price
1000	**1**	**Left - Fixed - Right**	**111**	**$3,961.30**	**$3,961.30**

RO Size: 139 1/2" x 66 1/2" **Unit Size: 139" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
CAX 2' 9"X5' 6" - SCA6056 - CAX 2' 9"X5' 6", Unit, Unit 1, 3: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Unit 3: Right, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Insect Screen 1: E-Series Casement, CAX 33 x 66 Full Fiberglass White
Insect Screen 1: E-Series Casement, CAX 33 x 66 Full Fiberglass White

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	61.3125	12.4009
B1	0.29	0.32		C1	29.1250	61.3125	12.4009
C1	0.3	0.28					



Item	Qty	Operation	Location	Unit Price	Ext. Price
1100	**1**	**Stationary-Right**	**112**	**$5,372.34**	**$5,372.34**

RO Size: 84 1/2" x 92 1/2" **Unit Size: 84" x 92"**

AFRS 7'X7' 8", Unit, E-Series Gliding Door 2 Panel-AFRS, 4 9/16" Frame Depth, Factory Assembled, Rigid Vinyl w/Integral Vinyl Drip Cap, Bronze - Painted On-Floor Sill, 4 11/16" Stile Width, 4 11/16" Top Rail Height, 8" Bottom Rail Height, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Stationary-Right, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Albany, White, White, White, 2604, Full Screen, Fiberglass, Top Hung Gliding
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Head and Side Member Extension Jambs, Factory Applied

Trim Set 1: AFRS Stationary-Right Albany White PN:9007538
Auxiliary Foot Lock 1: AFRS White PN:1997301
Insect Screen 1: E-Series Gliding Door 2 Panel-AFRS, AFRS 84 x 92 Full Screen Fiberglass Top Hung Gliding White 2604

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.32	0.27	NO	A1	33.4375	88.0625	20.4485



Item	Qty	Operation	Location	Unit Price	Ext. Price
1200	**1**	**Left-Stationary**	**113**	**$5,372.34**	**$5,372.34**

RO Size: 84 1/2" x 92 1/2" **Unit Size: 84" x 92"**

AFRS 7'X7' 8", Unit, E-Series Gliding Door 2 Panel-AFRS, 4 9/16" Frame Depth, Factory Assembled, Rigid Vinyl w/Integral Vinyl Drip Cap, Bronze - Painted On-Floor Sill, 4 11/16" Stile Width, 4 11/16" Top Rail Height, 8" Bottom Rail Height, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Left-Stationary, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Albany, White, White, White, 2604, Full Screen, Fiberglass, Top Hung Gliding
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Head and Side Member Extension Jambs, Factory Applied

Trim Set 1: AFRS Left-Stationary Albany White PN:9007538

Auxiliary Foot Lock 1: AFRS White PN:1997301

Insect Screen 1: E-Series Gliding Door 2 Panel-AFRS, AFRS 84 x 92 Full Screen Fiberglass Top Hung Gliding White 2604

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.32	0.27	NO	A1	33.4375	88.0625	20.4485



Item	Qty	Operation	Location	Unit Price	Ext. Price
1300	**1**	**Fixed**	**114**	**$2,039.28**	**$2,039.28**

RO Size: 84 1/2" x 92 1/2" **Unit Size: 84" x 92"**

SCA 7'X7' 8", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.32	0.32	NO

Item	Qty	Operation	Location	Unit Price	Ext. Price
1400	**1**	**Left - Fixed - Fixed - Right**	**115**	**$6,028.32**	**$6,028.32**



RO Size: 184" x 91" **Unit Size: 183 1/2" x 90 1/2"**

Mull: Job Site Mulled, Field Ribbon Mull, 1/2 Inch Mull Material
CAX 2' 9"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - CAX 2' 9"X7' 6 1/2", Unit, Unit 1, 4: E-Series Casement, Unit 2, 3: E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Pine w/White - Painted Interior Frame, Pine w/White - Painted Interior Sash/Panel, Unit 1: Left, Unit 2, 3: Fixed, Unit 4: Right, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass
Wrapping: 6 9/16" One Piece Step Jamb w/Interior Extension Jamb Pine / White - Painted Standard Individual Units (Boxed) Complete Unit Extension Jambs, Job Site Applied

CAX 2' 9"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - CAX 2' 9"X7' 6 1/2", Unit, E-Series Casement, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Pine w/White - Painted Interior Frame, Pine w/White - Painted Interior Sash/Panel, Left, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass

CAX 2' 9"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - CAX 2' 9"X7' 6 1/2", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Pine w/White - Painted Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer

CAX 2' 9"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - CAX 2' 9"X7' 6 1/2", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Pine w/White - Painted Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer

CAX 2' 9"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - SCA 4' 10"X7' 6 1/2" - CAX 2' 9"X7' 6 1/2", Unit, E-Series Casement, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Pine w/White - Painted Interior Frame, Pine w/White - Painted Interior Sash/Panel, Right, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper, White, Full, Fiberglass

Insect Screen 1: E-Series Casement, CAX 33 x 90.5 Full Fiberglass White

Insect Screen 1: E-Series Casement, CAX 33 x 90.5 Full Fiberglass White

Extension Jamb 1: CAX 183.5 x 90.5 One Piece Step Jamb w/Interior Extension Jamb Standard Pine White - Painted 6 9/16" Complete Unit Extension Jambs Job Site Applied

Nailing Flange: CAX 183.5 x 90.5 Rigid Vinyl w/Integral Vinyl Drip Cap Complete Unit Job Site Applied

Job Site Join Mull Material: E-Series Vertical, Field, Job Site Mulled, 1/2 Inch Reinforced, 0.5" thick, 90.5" length, White / Pine White - Painted

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	85.8125	17.3562
B1	0.32	0.32		D1	29.1250	85.8125	17.3562
C1	0.32	0.32					
D1	0.3	0.28					



Item	Qty	Operation	Location	Unit Price	Ext. Price
1500	**1**	**Fixed-Fixed**	**116**	**$3,828.38**	**$3,828.38**

RO Size: 121" x 90 1/2" **Unit Size: 120 1/2" x 90"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
SCA 5'X7' 6"-SCA 5'X7' 6", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" One Piece Step Jamb w/Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Individual Units (Boxed) Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.32	NO
B1	0.29	0.32	



Item	Qty	Operation	Location	Unit Price	Ext. Price
1600	**1**	**Fixed**	**117**	**$2,051.59**	**$2,051.59**

RO Size: 72 1/2" x 90 1/2" **Unit Size: 72" x 90"**

SCA 6'X7' 6", Unit, E-Series Picture Window, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" One Piece Step Jamb w/Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.32	0.32	NO



Item	Qty	Operation	Location	Unit Price	Ext. Price
1700	**1**	**Stationary**	**118**	**$2,820.64**	**$2,820.64**

RO Size: 42 1/2" x 108 1/2" **Unit Size: 42" x 108"**

AFDI 3' 6"X9', Unit, E-Series Inswing Door-1 Panel-Contemporary, Standard Panel, 6 9/16" Frame Depth, Factory Assembled, Exterior Trim Installation Flange, Clear Anodized On-Floor Drainage Sill, 3 11/16" Stile Width, 3 11/16" Top Rail Height, 3 11/16" Bottom Rail Height, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Stationary, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 2" Ovolo Brickmould 3-Sided White 2604 Factory Applied Exterior Trim

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.33	0.22	NO



Item	Qty	Operation	Location	Unit Price	Ext. Price
1800	**1**	**Fixed-Fixed**	**201**	**$3,238.79**	**$3,238.79**

RO Size: 133" x 66 1/2" **Unit Size: 132 1/2" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
SCA5656-2, Unit, E-Series Picture Window, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.29	0.32	NO
B1	0.29	0.32	



Item	Qty	Operation	Location	Unit Price	Ext. Price
1900	**1**	**Left - Fixed - Right**	**202**	**$4,087.01**	**$4,087.01**

RO Size: 121 1/2" x 66 1/2" **Unit Size: 121" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
CAX 2' 9"X5' 6" - SCA4656 - CAX 2' 9"X5' 6", Unit, Unit 1, 3: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Unit 3: Right, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	61.3125	12.4009
B1	0.29	0.33		C1	29.1250	61.3125	12.4009
C1	0.3	0.28					



Item	Qty	Operation	Location	Unit Price	Ext. Price
2000	**1**	**Left**	**203**	**$1,413.96**	**$1,413.96**

RO Size: 33 1/2" x 66 1/2" **Unit Size: 33" x 66"**

CAX 2' 9"X5' 6", Unit, E-Series Casement, 2 7/8" Frame Depth, Exterior Trim Installation Flange, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Left, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	61.3125	12.4009



Item	Qty	Operation	Location	Unit Price	Ext. Price
2100	**1**	**Left**	**204**	**$1,350.20**	**$1,350.20**

RO Size: 36 1/2" x 66 1/2" **Unit Size: 36" x 66"**

CAX3056, Unit, E-Series Casement, 2 7/8" Frame Depth, Exterior Trim Installation Flange, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Left, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	32.1250	61.3125	13.6782



Item	Qty	Operation	Location	Unit Price	Ext. Price
2200	**1**	**Fixed-Right**	**205**	**$2,822.19**	**$2,822.19**

RO Size: 89" x 66 1/2" **Unit Size: 88 1/2" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
SCA4656-CAX 2' 10"X5' 6", Unit, Unit 1: E-Series Picture Window, Unit 2: E-Series Casement, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Fixed, Unit 2: Right, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.29	0.33	NO	B1	30.1250	61.3125	12.8267
B1	0.3	0.28					



Item	Qty	Operation	Location	Unit Price	Ext. Price
2300	**1**	**Left-Fixed**	**206**	**$2,822.19**	**$2,822.19**

RO Size: 89" x 66 1/2" **Unit Size: 88 1/2" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
CAX 2' 10"X5' 6"-SCA4656, Unit, Unit 1: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	30.1250	61.3125	12.8267
B1	0.29	0.33					



Item	Qty	Operation	Location	Unit Price	Ext. Price
2400	**3**	**Left**	**207-208-209**	**$1,413.96**	**$4,241.88**

RO Size: 33 1/2" x 66 1/2" **Unit Size: 33" x 66"**

CAX 2' 9"X5' 6", Unit, E-Series Casement, 2 7/8" Frame Depth, Exterior Trim Installation Flange, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Left, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	61.3125	12.4009



Item	Qty	Operation	Location	Unit Price	Ext. Price
2500	**1**	**Left-Fixed**	**210**	**$2,822.19**	**$2,822.19**

RO Size: 89" x 66 1/2" **Unit Size: 88 1/2" x 66"**

Mull: Factory Mulled, Andersen Ribbon Mull, 1/2 Inch Mull Material
CAX 2' 10"X5' 6"-SCA4656, Unit, Unit 1: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Standard, High Performance Keeper
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	30.1250	61.3125	12.8267
B1	0.29	0.33					



Item	Qty	Operation	Location	Unit Price	Ext. Price
2600	**1**	**Left - Fixed - Right**	**picture window**	**$4,936.60**	**$4,936.60**

RO Size: 108 1/2" x 90 1/2" **Unit Size: 108" x 90"**

Mull: Factory Mulled, Andersen Ribbon Mull, Zero Mull Material
CAX 2' 9"X7' 6" - SCA 3' 6"X7' 6" - CAX 2' 9"X7' 6", Unit, Unit 1, 3: E-Series Casement, Unit 2: E-Series Picture Window, 2 7/8" Frame Depth, Exterior Trim Installation Flange, Direct Set (1 Piece), White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Unit 1: Left, Unit 2: Fixed, Unit 3: Right, Direct Set (1 Piece), Align w/Stationary Stops, Piano Hinge, Dual Pane Low-E4 Standard Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Handle w/Cover, White, Standard, High Performance Keeper, White, Full, Fiberglass
Wrapping: 2" Ovolo Brickmould 4-Sided White 2604 Factory Applied Exterior Trim, 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Factory Applied

WHT RH HARDWARE KIT CSMT BAG W6204PKRKW7 PN:9078352
Insect Screen 1: E-Series Casement, CAX 33 x 90 Full Fiberglass White
WHT LH HARDWARE KIT CSMT BAG W6204PKLKW7 PN:9078351
Insect Screen 1: E-Series Casement, CAX 33 x 90 Full Fiberglass White

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.3	0.28	NO	A1	29.1250	85.3125	17.2550
B1	0.29	0.33		C1	29.1250	85.3125	17.2550
C1	0.3	0.28					



Item	Qty	Operation	Location	Unit Price	Ext. Price
2700	**2**	**Stationary-Right**	**GLIDING DOOR**	**$4,806.85**	**$9,613.70**

RO Size: 72 1/2" x 92 1/2" **Unit Size: 72" x 92"**

AFRS 6'X7' 8", Unit, E-Series Gliding Door 2 Panel-AFRS, 4 9/16" Frame Depth, Factory Assembled, Rigid Vinyl w/Integral Vinyl Drip Cap, Bronze - Painted On-Floor Sill, 4 11/16" Stile Width, 4 11/16" Top Rail Height, 8" Bottom Rail Height, White 2604 Exterior Frame, White 2604 Exterior Sash/Panel, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Sash/Panel, Stationary-Right, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer, Albany, White, White, White, 2604, Full Screen, Fiberglass, Top Hung Gliding
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Head and Side Member Extension Jambs, Factory Applied

Trim Set 1: AFRS Stationary-Right Albany White PN:9007538

Auxiliary Foot Lock 1: AFRS White PN:1997301

Insect Screen 1: E-Series Gliding Door 2 Panel-AFRS, AFRS 72 x 92 Full Screen Fiberglass Top Hung Gliding White 2604

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	0.32	0.27	NO	A1	27.4375	88.0625	16.7793



Item	Qty	Operation	Location	Unit Price	Ext. Price
2800	**1**	**Fixed-Fixed**	**None Assigned**	**$6,183.83**	**$6,183.83**

RO Size: 84 1/2" x 126 1/2" **Unit Size: 84" x 126"**

Mull: Job Site Mulled, Field Ribbon Mull, 1 Inch Mull Material
CAUX 3' 5 1/2"X10' 6"-CAUX 3' 5 1/2"X10' 6", Unit, E-Series Spec Rectangle, 2 7/8" Frame Depth, Rigid Vinyl w/Integral Vinyl Drip Cap, Direct Set, White 2604 Exterior Frame, Vertical Grain Douglas Fir w/Unfinished Interior Frame, Fixed, Dual Pane Low-E4 Tempered Argon Fill Ovolo Glass Stop Stainless Glass / Grille Spacer
Wrapping: 6 9/16" Interior Extension Jamb Vertical Grain Douglas Fir / Unfinished Standard Perimeter Complete Unit Extension Jambs, Job Site Applied

Extension Jamb 1: CAUX 84 x 126 (for Standard Specialty Frame) Interior Extension Jamb Standard Vertical Grain Douglas Fir Unfinished 6 9/16" Complete Unit Extension Jambs Job Site Applied

12IN, INSTALL STRAP KIT WITH SCREWS QTY 20 PN:9198583

Nailing Flange: CAUX 84 x 126 Rigid Vinyl w/Integral Vinyl Drip Cap Complete Unit Job Site Applied

Job Site Join Mull Material: E-Series Specialty Vertical, Field, Job Site Mulled, 1 Inch Reinforced, 1" thick, 126" length, White / Vertical Grain Douglas Fir Unfinished

Unit #	U-Factor	SHGC	ENERGY STAR
A1	0.28	0.35	NO
B1	0.28	0.35	



Item	Qty	Operation	Location	Unit Price	Ext. Price
2900	**1**	**5L**	**FOLDING DOOR WITH SCREEN DOOR**	**$33,776.31**	**$33,776.31**

RO Size: 220 3/4" x 120 1/4" **Unit Size: 220" x 119 1/2"**

AFOCD 18' 4"X9' 11 1/2", Unit, Contemporary Clad Wood Folding Outswing Door, -1 Base Jamb Depth, 6 9/16" Frame Depth, Unassembled, Bronze - Painted On-Floor Drainage Sill, 3 11/16" Stile Width, 3 11/16" Bottom Rail Height, White 2605 Exterior Frame, White 2605 Exterior Sash/Panel, w/White - Painted Interior Frame, w/White - Painted Interior Sash/Panel, 5 Panel, 5L, Dual Pane Low-E4 Tempered Argon Fill Contemporary Glass Stop Stainless Glass / Grille Spacer, Tribeca, White, Satin Stainless Steel, White Panel Stop, Exterior Keyed Lock, 36" from Bottom of Panel, White, Full Screen, Retractable, Interior Insect Screen Location

Frame: AFOCD, AFOCD 18' 4"X9' 11 1/2", 6 9/16", White Exterior/ White - Painted Interior White - Painted 5L, On-Floor Drainage

Trim Set 1: AFOCD Tribeca White PN:2577555

WHT 2 1/4 HDWRE KIT 2017 PN:9172429

Panel Stop 1: AFOCD White PN:2579687

Exterior Keyed Lock 1: AFOCD 5L Tribeca White PN:2579721

Insect Screen 1: Contemporary Clad Wood Folding Outswing Door, AFOCD Frame Head and Sill Retractable White w/Charcoal Mesh

Insect Screen 2: Contemporary Clad Wood Folding Outswing Door, AFOCD Side Jamb Retractable White w/Charcoal Mesh

Slab 1 43 15/32" X 115 5/32" AFOCD, 5L, White/ White - Painted, Low-E4 Tempered Argon Filled, Satin Stainless Steel Hinge

Slab 2 43 15/32" X 115 5/32" AFOCD, 5L, White/ White - Painted, Low-E4 Tempered Argon Filled, Satin Stainless Steel Hinge

Slab 3 43 15/32" X 115 5/32" AFOCD, 5L, White/ White - Painted, Low-E4 Tempered Argon Filled

Slab 4 43 15/32" X 115 5/32" AFOCD, 5L, White/ White - Painted, Low-E4 Tempered Argon Filled

Slab 5 43 15/32" X 115 5/32" AFOCD, 5L, White/ White - Painted, Low-E4 Tempered Argon Filled, Satin Stainless Steel Hinge

Unit #	U-Factor	SHGC	ENERGY STAR	Clear Opening/Unit #	Width	Height	Area (Sq. Ft)
A1	---	---	NO	A1	205.037	114.268	162.703

Customer is responsible to verify all quantities, sizes, styles, colors, etc. on this quote. Andersen is non-returnable. All Andersen orders will be invoiced 60 days after being received at Blue Ridge Lumber.

SUB-TOTAL:	$140,469.06
FREIGHT:	$0.00
LABOR:	$0.00
TAX:	$9,306.08
TOTAL:	$149,775.14

CUSTOMER SIGNATURE_____DATE_____

* All graphics as viewed from the exterior. ** Rough opening dimensions are minimums and may need to be increased to allow for use of building wraps or flashings or sill panning or brackets or fasteners or other items.

Thank you for choosing Andersen Windows & Doors