GenServe Inc.
Branch Office
99 Castleton Street
Pleasantville, NY 10570
914.305.8671
www.genserveinc.com

QUOTATION AGREEMENT

Steadfast Electrical Contracting
34-18 Northern Boulevard
Long Island City, NY 11101

February 25, 2026
Quotation # LB 4356

Project: 18 Vesey Street

Attn: Michael Cabrera

We are pleased to submit our proposal for Taylor equipment as follows:

Qty (1): TD80 (outdoor)

DESCRIPTION

- 80kW/100kVA, standby, 120/208 volt, three phase, 4 wire, 60 Hz, 1800 RPM
- UL 2200 Listed and Labeled
- Stamford UCI274C311 Alternator, 278 amps
- Basler DGC2020 Controller
- **Spring Isolators**

FUEL

- Diesel

COOLING SYSTEM ACCESSORIES

- Block Heater 1500 W
- Skid mounted radiator
- Water drain valve

FACTORY SOUND ATTENUATED WEATHER PROOF ENCLOSURE

- Enclosed insulated silencer with tailpipe & rain cap
- **Sound Containment Floor (Required to maintain sound rating)**
- Skid mounted, fully corrosion-resistant material construction
- Rodent Guards

FUEL SYSTEM

- 200 Gallon Sub Base Fuel Tank (UL 142) NYC Certified
- 200 % Rupture Basin; Double Wall Secondary Containment
- Supply/Return Dip Tube Package
- Low-Level and High-Level Alarms
- Fuel in Basin Alarm; Basin Drain; Fuel Level Gauge; Emergency Vents
- Fire Rated Fuel Lines; Standard Electrical Stub up area
- Isolator Pad Support Plate; Removable End Plate

LINE CIRCUIT BREAKER

- 200 amp, 100 % rated, Thermal Magnetic
- 100 amp, 100 % rated, Electronic Trip
- 100 amp, 100 % rated, Electronic Trip
- 30A Fused Disconnect (shipped loose for installation by others)

ENGINE ELECTRICAL ACCESSORIES

- Battery Rack & Cables; 12V starting battery
- Battery charger, float with alarms, 24V-10A

ENGINE AND GENERATOR ACCESSORIES

- Operation and maintenance manuals
- Lube oil & coolant; Oil drain extension; Electronic isochronous governor
- Local emergency stop button
- Remote emergency stop button (shipped loose for installation by others)
- Run relay, 24V
- RSAIII remote annunciator (shipped loose for installation by others)
- Air filter restriction indicator

ASCO 300 SERIES AUTOMATIC TRANSFER SWITCH

- 104 amp, 3 pole, 208 volt, standard transition, 3ph, 4w, Nema 1
- 200 amp, 3 pole, 208 volt, standard transition, 3ph, 4w, Nema 1
- 70 amp, 3 pole, 208 volt, standard transition, 3ph, 4w, Nema 1
- 70 amp, 3 pole, 208 volt, standard transition, 3ph, 4w, Nema 1

WARRANTY

- Two Year warranty on generator
- Two Year warranty on transfer switches

DEALER SERVICES

- Certified factory test report
- Basic Factory Startup

TOTAL EQUIPMENT PACKAGE PRICE: $84,095.00

(plus applicable sales tax)

LEAD TIME:

Generator: **Estimated 38 weeks ARO**
Transfer Switches: **Estimated 7 weeks ARO**

EXCLUSIONS:

1) **All 3rd party testing requirements – including but not limited to NETA, Transient & Harmonic Content Recording, etc. is not included in above price and is to be performed/supplied by others.**

NOTES:

1) **Startup commissioning service per factory guidelines is included in the proposal**
2) **Above price does not include any applicable federal, state or local taxes.**
3) Above price is for the supply of equipment only and does not include installation, offloading, mounting, fuel line, fuel source, engineering requirements etc.. Customer is responsible for final approval of purchased equipment.
4) Above price does not include bollards, concrete mounting pad, dunnage, or anchoring.
5) **Price includes FOB common carrier freight. Offloading, rigging, and setting are excluded**
6) All quotations are subject to review and revision.
7) **Above price is based on project drawing(s) E-104 & E-300 sent to GenServe. No written specifications for this project were viewed by or supplied to GenServe.**
8) **Inclusion of any product or requirement not listed in this proposal shall not be assumed, regardless of specification, unless agreed upon in writing by both parties.**
9) All new generator systems must have a certified factory start-up performed within six (6) months of unit delivery to jobsite, unless otherwise agreed upon in writing. A transfer to emergency power is required to complete system adjustments and validate warranty at startup. All Start-up labor is performed during normal business hours only. (M-F 7:30 AM to 3:30 PM).
10) **Ship dates are best estimates only and are subject to change. GenServe is not responsible for incidental or liquidated damages.**
11) **Pricing reflects packaged discounts and assumes release of all equipment concurrently. Individual select equipment releases are subject to itemized price revisions.**
12) Customer is responsible for any required permits, filing fees, town or city clearances that may be required.
13) All covered warranty labor is performed during normal business hours only. (M-F 7:30 AM to 3:30 PM). Overtime labor and overtime emergency service calls are not covered under warranty and will be billed portal to portal. All warranty time periods will automatically begin six (6) months after unit delivery to jobsite.
14) If, after the effective date of this agreement, any new or amended tariffs, duties, or import taxes are imposed on materials or components used in the manufacture of the goods covered by this agreement, GenServe shall have the right to adjust the contract price to reflect the increase in costs directly attributable to such new or amended tariffs, duties, or taxes, upon providing written notice to [the Buyer] with supporting documentation.

TERMS:

1) Payment terms are NET 30 days subject to credit approval. Credit approval is required regardless of any other agreement.
2) Payment is not contingent on buyer's ability to collect or obtain funds from any other party.
3) All C.O.D orders (if applicable) require a 50% deposit to process an order. All Invoice balances of in stock equipment are due upon equipment delivery to job site.
4) All non-stock equipment invoice balances are due within ten (10) days after equipment arrives at GenServe warehouse.
5) All equipment that is ready for shipment from the factory will be invoiced in full regardless of site preparedness.
6) Any equipment that is held for shipment from the factory will be invoiced all factory storage charges.
7) All partial shipments will be invoiced at time of delivery.
8) All credit card payments will be billed with an additional 2.5% credit card processing fee.
9) All final payments are due prior to system start up and warranty validation. No retainages are allowed.
10) All deposits are non-refundable.
11) Any orders cancelled while in submittal process will be invoiced for all factory engineering charges.
12) Cancellation of a released order will be charged a cancellation charge for all submitted drawings, factory documents, and any manufactured items including factory cancelation policy charges.
13) All sales are final.
14) All proposals are valid for thirty (30) days.

I appreciate the opportunity to help and serve you with your emergency power needs. Should you have any questions or require further information, please feel free to call me or email me at any time.

Sincerely,

Louis Baldessarre
GenServe LLC

*** If in agreement with the above terms and conditions, please sign below and return all pages – Thank you.**

AUTHORIZED SIGNATURE:_____DATE:_____

PRINT FULL NAME:_____TITLE:_____

P.O.#:_____AMOUNT:_____

Note: All signed quotation agreements must be accompanied by company purchase order.