Date: 12/23/2024

Quotation

Quotation No.: **1319**

Project: Crest House - Cold Spring, NY

Position	Quantity	Description	Total [$]
W1-TOP Exterior View	1 Pcs		



Window Element 54 7/8" x 87 3/4"
W1 Top / Corner, Consisting of a Fixed Field.
System: Crystal W50 Window wall
Colours: Standard Color 2604 Finish
Profiles: Mill finish GW
Glazing:
1 x G1T
Wall Connection:
BYPASS-TOP-3
SIDE JAMB-2

W1-BOT Exterior View	1 Pcs		



Window Element 54 7/8" x 98 1/4"
W1 Bottom / Corner, Consisting of a Fixed Field.
System: Crystal W50 Window wall
Colours: Standard Color 2604 Finish
Profiles: Mill finish GW
Glazing:
1 x G1T
Wall Connection:
SIDE JAMB-2
SLAB-BO-3

W2-TOP Exterior View	1 Pcs		



Door Element 323 3/4" x 87 3/4"
W2 Top / Corner, Consisting of six Fixed Fields and a Single Door.
System: Crystal W50 Window wall
Door Description:
Door Single open Out Left Hand Reverse
Colours: Standard Color 2604 Finish
Profiles: Mill finish GW
Glazing:
6 x G1T
1 x G3T (DOOR)
Wall Connection:
BYPASS-TOP-3

Position	Quantity	Description	Total [$]
W2-BOT	1 Pcs		
Exterior View			
		**Door Element 323 3/4" x 98 1/4"** **W2 Bottom / Corner**, Consisting of five Fixed Fields and two Single Doors. System: Crystal W50 Window wall Door Description: Doors Single open Out Right Hand Reverse Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 5 x G1T 2 x G3T (DOOR) Wall Connection: SLAB-BO-3	
W3-TOP	1 Pcs		
Exterior View			
		**Window Element 197 5/8" x 87 3/4"** **W3 Top / Corner**, Consisting of four Fixed Fields. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 4 x G1T Wall Connection: BYPASS-TOP-3 SIDE JAMB-2	
W3-BOT	1 Pcs		
Exterior View			
		**Window Element 197 5/8" x 98 1/4"** **W3 Bottom / Corner**, Consisting of four Fixed Fields. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 4 x G1T Wall Connection: SLAB-BO-3 SIDE JAMB-2	

Position	Quantity	Description	Total [$]
W4	1 Pcs		
Exterior View			
		**Window Element 111 5/8" x 67"**, Consisting of a Fixed Field and a Side Hung Window. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 1 x G1T 1 x G2T(1.25"IGU) Window Hardware: W50 INSWING Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	
W5	1 Pcs		
Exterior View			
		**Window Element 123 5/8" x 67"**, Consisting of a Fixed Field and a Side Hung Window. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 1 x G1T 1 x G2T(1.25"IGU) Window Hardware: W50 INSWING Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	
W6	1 Pcs		
Exterior View			
		**Window Element 168 1/4" x 67"**, Consisting of two Side Hung Windows and a Fixed Field. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 2 x G2T(1.25"IGU) 1 x G1T Window Hardware: W50 INSWING Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	

Position	Quantity	Description	Total [$]
W8	1 Pcs		
Exterior View 		**Window Element 681 3/8" x 67"**, Consisting of eleven Side Hung Windows, six Fixed Fields and a Top Hung Window. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 12 x G2T(1.25"IGU) 6 x G1T Window Hardware: W50 INSWING W50 PROJECT OUT (AWING) Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	
W9	5 Pcs		
Exterior View 		**Window Elements 46" x 67"**, Consisting of a Fixed Field. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 1 x G1T Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	
W10	3 Pcs		
Exterior View 		**Window Elements 66" x 67"**, Consisting of a Fixed Field. System: Crystal W50 Window wall Colours: Standard Color 2604 Finish Profiles: Mill finish GW Glazing: 1 x G1T Wall Connection: BYPASS-TOP-3 SIDE JAMB-2 SLAB-BO-3	

Position	Quantity	Description	Total [$]
W11	1 Pcs		

Exterior View



Window Element 204" x 60", Consisting of three Fixed Fields.
System: Crystal W50 Window wall
Colours: Standard Color 2604 Finish
Profiles: Mill finish GW
Glazing:
3 x G1T
Wall Connection:
BYPASS-TOP-3
SIDE JAMB-2
SLAB-BO-3

W12	1 Pcs		

Exterior View



Window Element 58" x 46", Consisting of a Fixed Field.
System: Crystal W50 Window wall
Colours: Standard Color 2604 Finish
Profiles: Mill finish GW
Glazing:
1 x G1T
Wall Connection:
BYPASS-TOP-3
SIDE JAMB-2
SLAB-BO-3

Grand Total Net
Value Added Tax
Total Price

Total Square Feet: **1,551.76**
Total Fixed Lite: **42**
Total Operable: **16**
Total Door: **3**

REMARK:

1) Standard Color AAMA 2604 finish powder coating (10-year warranty)
2) Exclusion: Field testing; fasteners; shim; drip caps; slab cover; storefront, curtainwall, standalone louver, mech louver; middle portion inbetween W1-TOP & W1-BOT, W2-TOP & W2-BOT, W3-TOP & W3-BOT; opening W7; keypad and doorbell for door
3) Reconfiguration:
   W1, W2, &, W3 are quoted as separate top and bottom opening: W1-TOP & W1-BOT, W2-TOP & W2-BOT, W3-TOP & W3-BOT
   Maximum width for fixed lites are 60": operable lite are resized to maximum 48" width and adjacent lites resized to maintain opening size
4) (4) lengths of corner mullion included

QUOTATION:

1.Prices effective for 10 days from Quotation Date
2.Please inspect this document and notify us at once of any errors or changes, failure to do so relieves Crystal of any liability for errors or omissions; signing the packing list means, you are accepting delivery and the products without objection.
3.Crystal makes no other EXPRESS OR IMPLIED warranty except as stated.
4.Lead Time: _____
5.Delivery charges may be applicable on this order and are dictated by the total dollar value of the order and delivery location [ ] Box must be checked to request complete delivery shipments. Crystal's standard procedure is to make installment delivery shipments.
a request for complete delivery shipments may request complete delivery shipments. Crystal's standard procedure is to make installment delivery shipments; a request for complete delivery shipments may extend original delivery date.
6.Delivery commitment and lead time will be counted from the date all approvals have been received, accepted, and signed by both the customer and Crystal management; including credit approval, any/all deposits required, and shop drawings/window schedule approvals including specifications.
7.This quotation is subject to Crystal's General Terms and Conditions of Sales as set forth on Crystal's website (https://crystalwindows.com) but if Crystal products exceed maximum tested dimensions, they are warranted only against defects in glass components or paint finishes in accordance with Crystal's limited warranty set forth on Crystal's website. Crystal makes no other EXPRESS OR IMPLIED warranty.
8.The Crystal products above are custom-manufactured to your specifications and you have agreed to the payment terms as stated. This order may be subject to freight, delivery, and storage charges.
9.All payments remitted by credit card shall be subject to additional finance charge of 3%.
10.Prior authorization from Crystal is required for any returns.
11.Crystal is required by law to charge and remit sales tax in certain States, based on the delivery address of the order, unless the Buyer provides Crystal with a tax exemption certificate. In all other States it is the Buyer's responsibility to pay the sales tax (or use tax) directly to the appropriate State taxing authority.
12.Buyer may request that Crystal warehouse the goods at Crystal's factory rather than accept them on the delivery date. Such arrangements may be available if Crystal has sufficient storage room at the time of Buyer's request. In such event, Crystal will add a charge for storage of $5.00 per window/per day and $10.00 per door/per day, and the balance of the price must be paid prior to the storage of the goods. Storage fees may be deducted from the Buyers's deposit.
13.Crystal may elect to cancel a sale if Buyer fails to pick up the goods from Crystal's factory within 30 days after the goods are ready for delivery. Buyer shall remain obligated to pay for all goods completed and in the process of being manufactured prior to Crystal's consent to the Buyer's cancellation as well as any storage fees incurred (See #12 above).
14.Please add $3000.00 (net) to the total amount if a full set of shop drawings is required.
15.Field tests and professional engineering calculations are not included.
16.For any products delivered to the Customer more than 90 days after the Purchase Order contract is entered into by the parties, the purchase price for those products may be subject to a Surcharge because of future increases in Crystal's production costs at the time of delivery (including the cost of raw materials). Depending on the discount rate calculation at the time of the Purchase Order, the Customer may be entitled to a partial reduction of any Surcharge (an "Allowance") of zero percent (0%) to six percent (6%). This Allowance would be subtracted from the Surcharge.